

1 010023

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,048 - 00/RE

NW SW, SEC. 6, T 26 S, R 11 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692

Operator: American Petrofina Co. of Texas
Name & Address: 1601 NW Expressway, Suite 900
Oklahoma City, OK 73118

1980 feet from S section line

4620 feet from E section line

Lease Name Schlenz Well # 2

County Pratt 134.91

Well Total Depth 4151 feet

Conductor Pipe: Size feet

Surface Casing: Size 9 5/8 feet 950

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 pm Day: 29 Month: August Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4151' Perfs at 3640-46'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls,

release 9 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 pm Day: 29 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls, released 9 5/8" rubber plug and pumped 150 sx cement.

RECEIVED 9-6-85
STATE CORPORATION COMMISSION

SEP 6 1985

Maximum pressure 800 psi and shut in 300 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1969' 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 10 1985

Signed [Signature] (TECHNICIAN)

INV. NO. 9908