

6-19 89
API NUMBER 15- 151-21,509 - 00-00
SE NW, SEC. 6, T 26 S, R 11 W/R

3300 feet from S section line
3300 feet from E section line

Lease Name Bookstore Well # 1-6
County Pratt 133.67

Well Total Depth 4113 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 363

To: 1 120268
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Operator: W.L. Kirkman, Inc.

Name & Address P.O. Box 782290

Wichita, KS 67278-2290

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 19 Month: 6 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4113' Perfs at 2984-96, 3841-43, 3942-68'

1st plug sand back to 2930' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 19 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 2934' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Pumping pressure 0-300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-27-89
INV. NO. 25129
6-19

Signed _____ (TECHNICIAN)

6-26-89
RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1989
CONSERVATION DIVISION
Wichita, Kansas