

214

2-010091

KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2125  
Wichita, KS 67202

1-16

API NUMBER: 15-155-21,374 - 0000

SE SE NW SEC 33 , T 22 S, R 10W

OPERATOR LICENSE # 31798

3040 FEET FROM S SECTION LINE

OPERATOR: Xanadu Exploration Co.

2970 FEET FROM E SECTION LINE

NAME & 6 E. 5th St., Suite 200

LEASE NAME: Bowen WELL # 1-33

ADDRESS: Tulsa, OK 74103

COUNTY: Reno

WELL TOTAL DEPTH: 3787' 123.07

CONDUCTOR PIPE: @

SURFACE CASING: 8 5/8" @ 210'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_ X \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR L. D. Drilling, Inc.

ADDRESS: RR 1, Box 183B, Great Bend KS 67530 LICENSE: 6039

COMPANY TO PLUG AT: HOUR: 16:00 DAY: 16 MONTH: January YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM Bessie DeWerff

COMPANY NAME: L. D. Drilling, inc. PHONE: 316-793-3051

WERE: Fill hole with heavy mud. Spot plugs through drill pipe. Spot 35 sacks cement at 3700', spot 35 sacks cement at 1400', spot 35 sacks cement, spot 70 sacks cement at 260', spot 10 sacks cement at 40', fill rathole with 15 sacks cement, and fill mousehole with 10 sacks cement.

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { x }

COMPLETED: HOUR: 20:30 DAY: 16 MONTH: January YEAR: 1996

ACTUAL PLUGGING REPORT: Filled hole with heavy mud. Spotted cement through drill pipe. Spotted 35 sacks cement at 3700', spotted 35 sacks cement at 1400', spotted 35 sacks cement at 900', spotted 70 sacks cement at 250', spotted 10 sacks cement at 40', and filled rathole with 15 sacks cement.

REMARKS: Used 60/40 pozmix with 4% gel by Halliburton - Invoice #906979

I DID NOT OBSERVE THIS PLUGGING.

RECEIVED  
KANSAS CORPORATION COMMISSION  
4-9-1996  
APR 09 1996

Michael R. Wilson  
Michael R. Wilson

AGENT  
CONSERVATION DIVISION  
FORM CR#2/3  
REV. 3/90

INVOICED

DATE 4-10-96

INV. NO. 45168

DW