

6-1515-155-19161-0000

2-100622

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15- 5/17/37

SE , SECTION 19 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 6718

330 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE

OPERATOR Fell Oil & Gas Co.
NAME & Box 466
ADDRESS Chase, KS 67524

LEASE NAME: Westfahl #A-6COUNTY: RenoWELL TOTAL DEPTH: 3384' - 109.98PIPE: 4-1/2" @ 3380'PIPE: 7" @ 3333'SURFACE CASING: 10-3/4" @ 522'PIPE: 16" @ 141'ABANDONED OIL WELL X GAS WELL INPUT WELL SMD D&A OTHER WELL AS HEREINAFTER INDICATED: Perf 2970-78'PLUGGING CONTRACTOR: Kelso Casing PullingADDRESS: Box 347, Chase, KS 67524 LICENSE: 6050COMPANY TO PLUG AT: HOUR: 2:00 DAY: 14 MONTH: 6 YR: 1990PLUGGING PROPOSAL RECEIVED FROM: Jim MeekCOMPANY NAME: Kelso Casing Pulling PHONE:

WERE: Sand 50' above top perf - 10 sx cmt - shoot & pull
pipe to 700' - pump cmt to circ 50' up into 10-3/4"
w/250 sx cmt - pull pipe to 200' & circ to surf after
4-1/2" & 7"

PLUGGING PROPOSAL RECEIVED BY: J. L. SandersPLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()COMPLETED: HOUR: 5:00p DAY: 15 MONTH: 6 YEAR: 1990

ACTUAL PLUGGING REPORT:

Sanded bottom to 2920' & dumped 4 sx cmt w/bailer -
shot & pulled 1941' of 4-1/2" - shot & pulled 1824' of
7" - ran 750' of 1" and pumped 375 sx cmt to surf - ran
3 jts of 1" dwn back side of 10-3/4" - circ 43 sx cmt
to surf.

REMARKS: United #350 - 375 sx 60/40 #351 43 sx 60/40

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE: 8-23-90INV. NO. 29036

J. L. Sanders
J. L. Sanders (AGENT)

RECEIVED
STATE CORPORATION COMMISSION

8-20-90
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90