

To: 2 100235  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

JUN 26 1987  
API NUMBER 15- 095-21,468 - 0000  
C N/2 SE SEC. 12, T 27 S, R 6 WXX  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8411  
Operator: Grury Management Company  
Name & Address 150 W. John Carpenter Freeway  
Irving, TX 75039

Lease Name Georing Well # 8  
County Kingman 94.25  
Well Total Depth 2900 PBD 2870 feet  
Conductor Pipe: Size 4 1/2" feet 2899 100sx  
Surface Casing: Size 8 5/8 feet 266 125sx

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated Perf 2814-24, 4 shots

Plugging Contractor Gressel Oilfield Services, Inc. License Number 3004  
Address Box 607, Burrton, KS

Company to plug at: Hour: AM Day: 19 Month: 6 Year: 1987

Plugging proposal received from George  
(company name) Gressel Oilfield Services, Inc. (phone) 463-5161

were: Fill 4 1/2" 50' above perf with sand, dump 5 sxs cement w/dump bailer. Shoot off pipe  
and pull. Build wood and rock bridge 50' below surface and fill with redi mix.

Plugging Proposal Received by J. L. Sanders  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: AM Day: 20 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT Sand bottom from 2849 to 2760 and dump 5 sxs cement with dump  
bailer. Shot pipe off and pulled 1837' of 4 1/2". Build bridge at 350 to 310 and filled  
with redi mix

RECEIVED  
STATE CORPORATION COMMISSION

JUN 30 1987

6-30-87

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Andale Redimix did the cementing  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I did not observe this plugging.

DATE 7-1-87

WV. NO. 17391

Signed J. L. Sanders  
(TECHNICIAN)