

2 100485

2-13

146
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 155-20,629-0000
SW, SEC. 19, T 23 S, R 7 W&E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3243
Operator: Commonwealth Petro. Inc.
Name & Address P. O. Box 2458
Hutchinson, KS 67504
316-463-5461

Lease Name Krehbiel Well # 1
County Reno 123.14
Well Total Depth 3789 feet
Conductor Pipe: Size 4-1/2" feet 3788
Surface Casing: Size 8-5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698
Address Box 108 Geneseo KS 67444

Company to plug at: Hour: 1:00p Day: 10 Month: 2 Year: 19 89

Plugging proposal received from Al Nicholas

(company name) Nicholas Casing (phone) 316-824-6338

work: Sand to 3715' & dump 4 sx cement - shoot & pull pipe - spot cement at 1150'
25 sx - 700' 25 sx - 300' 35 sx - gel to 60' & circ to surface.

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 2:00 p Day: 13 Month: 2 Year: 1989

ACTUAL PLUGGING REPORT Sand to 3715' & dumped 4 sx cement - shot & pulled 2980' of
4-1/2" to 1150' - circulated 25 sx cement - pulled pipe to 700' & circulated 25 sx
cement- pulled pipe to 300' & circ 35 sx cement and spacer w/gel to 60' & circ
cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1989

Remarks: 60/40 2% gel
If additional description is necessary, use BACK of this form
Wichita, Kansas

INVOICED

I (did / did not) observe this plugging.

DATE 3-30-89

INV. NO. 26295

WF

Signed J. L. Sanders
(TECHNICIAN)