

4-7-88

39 R

To: 1 120087
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,043-0000

SW NW NE, SEC. 21, T 24 S, R 13 W/E

4350 feet from S section line
2070 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4323

Lease Name Owen Well # 1 (OWWO)

Operator: Reichlinger Business Services

County Stafford 134.23

Name & Address Box 4

Well Total Depth 4130 feet

118 West 8th Street

Conductor Pipe: Size feet

York, Nebraska

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 7 Month: 4 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4129' CIBP at 4024 & 4078', Perfs at 3968-74'

1st plug sand back to 3915' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:15 a.m. Day: 7 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3915' and dumped 4 sx cement on top of sand through bailer;

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION APR 13 1988

Pumping pressure 0-700 psi and shut in 0 on the gauge in 5 minutes.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (copy to observe this plugging.)

Signed [Signature] (TECHNICIAN)

DATE 4-20-88

INV. NO. 20392