

To: 1 051495
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-7
API NUMBER 15- 185-22,812-0000 73
C W/2 NE, SEC. 21, T. 24 S, R. 13 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 30395
Operator: Iannitti Oil Company
Name & Address: P.O. Box 308
Great Bend, KS 67530

3960 feet from S section line
1980 feet from E section line
Lease Name Heyen Well # 1
County Stafford 132.99
Well Total Depth 4092 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 513

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drilling Company License Number 5122
Address P.O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 6 p.m. Day: 7 Month: 11 Year: 19 91

Plugging proposal received from Rich Wheeler
(company name) Woodman-Iannitti Drilling Company (phone) 316-792-1922

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 764-783'
1st plug at Arbuckle with 50 sx cement, 2nd plug at 780' with 40 sx cement,
3rd plug at 540' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 p.m. Day: 7 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 780' with 40 sx cement,
2nd plug at 540' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.
Water well plugged with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-18-91
NOV 18 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 12-4-91
INV. NO. 33925

Signed Richard W. Lacey (TECHNICIAN)