

1 080589

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,404-0000
^{SW} SE NW SW, SEC. 17, T. 24 S, R. 13 W/E
1650 feet from S section line
4590 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Lease Name Harrison Well # 1-17

Operator: Allen Drilling Company

County Stafford 135.85

Name & Address P.O. Box 1389

Well Total Depth 4180 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 815

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 9 p.m. Day: 1 Month: 1 Year: 19 87

Plugging proposal received from Alvin Carris

(company name) Allen Drilling Company (phone) 316-793-5877

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at top of Arbuckle with 30 sx cement,

2nd plug at 810' with 80 sx cement,

3rd plug at 400' with 80 sx cement. 4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:30 a.m. Day: 2 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 849' with 80 sx cement,

2nd plug at 417' with 80 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

JAN 6 1987

CONSERVATION DIVISION
Wichita, Kansas

1-6-87

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to ~~XXXXX~~) observe this plugging.

DATE 1-7-87

Signed J. A. [Signature]
(TECHNICIAN)

INV. NO. 15814