

To: 1 120141  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3476

Operator: Moff Oil Company

Name & Address 318 North Ninnescah

Pratt, KS 67124

10-5  
API NUMBER 15-185-21,339-0000

SW SE SE, SEC. 15, T 24 S, R 13 W/E

330 feet from S section line

990 feet from E section line

Lease Name Keller Well # 1

County Stafford 133.25

Well Total Depth 4100 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 5 Month: 10 Year: 1988

Plugging proposal received from Ted Moff

(company name) Moff Oil Company (phone) 316-672-7838

were: 5 1/2" at 4097' Open hole 4097-4100'

1st plug sand back to 4045' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 50 lbs. hulls, and 100 sx

cement  
STATE CORPORATION COMMISSION  
**RECEIVED**  
10-7-88

**OCT 7 1988**

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas  
Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 5 Month: 10 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4045' and dumped 5 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 50 lbs. hulls, and 100 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 65/35 Pozmix 5% gel by HOWCO. Casing recovery not available.  
(if additional description is necessary, use **BACK** of this form.)

**INVOICED**  
did not observe this plugging.

Signed Steve Durrant  
(TECHNICIAN)

DATE 10-10-88

INV. NO. 22563