

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 8530 EXPIRATION DATE June 30, 1983

OPERATOR Circle S Production, Inc. API NO. 15-185-21,787-0000

ADDRESS 112 W 3rd COUNTY Stafford
St Joh, KS 67576 FIELD

** CONTACT PERSON H I Soden PROD. FORMATION
PHONE 316-549-3585

PURCHASER LEASE SODEN

ADDRESS WELL NO. #1

DRILLING CONTRACTOR L. D. Drilling, Inc. 330 Ft. from North Line and

ADDRESS Rt #1, Box 183B 330 Ft. from East Line of
Great Bend, KS 67530 the NW (Qtr.) SEC 15 TWP 24 RGE 13 (W).

PLUGGING CONTRACTOR L. D. Drilling, Inc. WELL PLAT (Office Use Only)

ADDRESS Rt #1, Box 183B KCC
Great Bend, KS 67530 KGS

TOTAL DEPTH 4105' PBTD SWD/REP/

SPUD DATE 6-3-83 DATE COMPLETED 6-11-83 PLG. ✓

ELEV: GR 1910' DF KB 1915'

DRILLED WITH (XXXXX) (ROTARY) (X) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 313' DV Tool Used? no

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.


A F F I D A V I T

Don Popp, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Don Popp (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 15th day of June, 1983.



MY COMMISSION EXPIRES: 5-20-85

Bessie M DeWerff (Notary Public)

RECEIVED STATE CORPORATION COMMISSION JUN 1 6-11-83

** The person who can be reached by phone regarding any questions concerning this information.

REGULATION DIVISION Wichita Kansas

OPERATOR Circle S Production, Inc. LEASE SODEN SEC. 15 TWP. 24 RGE. 13

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 1

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				Anhy 762-781	
				Heebner 3382	
				Brn Lime 3513	
	Sand	0	120	Lansing 3543	
	Red Bed	120	762	Base K/C 3810	
	Anhy	762	781	Cong 3863	
	Shale	781	1620	Viola 3940	
	Line & Shale	1620	4105	Simp Shle 4032	
				Arbuckle 4084	
				RTD 4105	
<p>DST #1 3602 - 3625 Times: 30-30-60-45 Fair Blow thru 1st open, weak std blow thru 2nd open Rec: 270' Muddy SGC Salt Water. No show of oil IFP: 48-71 FFP: 95-150 ISIP: 1140 FSIP: 1062</p> <p>DST #2 3738 - 3760 Times: 30-30-30-30 Fair unsteady blow 3" in bucket 1st open. Very weak 2 min blow & died 2nd open. Rec: 50' Drilling Mud. Few oil specks in tool no gas or water IFP: 57-60 FFP: 60-62 ISIP: 736 FSIP: 226</p>					

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4"	8-5/8"	23	313'	60/40 POZ	275	2% Gel 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Estimated Production - I.P.	Oil bbls.	Gas MCF
	Water %	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)		Perforations