

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
OCT 10 1967
OIL & GAS DIVISION
WICHITA, KANSAS

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co., Inc. as this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.
Operator's full Name: Hellar Drilling Co., Inc. & H. C. Hopkins

Complete Address: 1014 Union Center Bldg., Wichita, Kansas

Lease Name: Suiter Well No. # 1

Location: C S/2 S/2 NW Sec. 23 Twp. 24 Rge. 13(E)(W) W

County Stafford Total Depth 4102' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

225' of 8 5/8" surface pipe, cement circulated with 185 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent