



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1972

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Zimmerman of Woodman Iannitti Drlg. has this date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: Woodman Iannitti Drlg. Co.

Complete Address: 1008 Union Natl Bldg. Wichita, KS

Lease Name: McCune Well No. 1

Location: SE/SE/NW Sec 24 Twp. 24s Rge. 13 (E)(W) W

County: Stafford Total Depth 4145 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zimmerman was instructed to plug the well as follows:

285 ft 8 5/8 surface pipe cemented with 200 sacks. Pump
40 sacks cement to 400 ft. 2nd plug at 250 ft with 25
sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks
cement to surface. 2 sacks cement in rat hole.

Pumped by Sun Oilwell Cementing Co. Great Bend, Ks

Very truly yours,

[Signature]
Conservation Division Agent