

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1965  
CONSERVATION DIVISION  
Wichita, Kansas

12-27-1965

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Otto Berens of Rex & Morris Drilling Co. has this

date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.  
Rex & Morris and McClure Oil Company  
Operator's full Name: and C. R. A., Inc.

Complete Address: P. O. Box 334, El Dorado, Kansas

Lease Name: Clowers Well No. # 1

Location: NE SE SE Sec. 35 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 4200' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Berens was instructed to plug the well as follows:

258' of 8 5/8" surface pipe, cement circulated with 225 sacks.  
Fill hole with drilling mud to 240', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent