

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10999-00-02⁰⁰
Spot: SENESE Sec/Twnshp/Rge: 29-24S-13W
1650 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: HOOVER Well Number: 1
County: STAFFORD Total Vertical Depth: 4191 feet

Operator License No.: 31793
Op Name: ROGERS, MERLIN D.
Address: RR 2, BOX 53
ST. JOHN, KS 67576

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 290 WITH 350 SX CMT
Production: Size 5.5 feet: 4188 WITH 135 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2002 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3750' & 5 SX CMT. 1ST PLUG AT 800' WITH 100# HULLS - 15 SX GEL - 50 SX CMT. 2ND PLUG AT 240' WITH 100# HULLS - 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2002 1:19 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3880'. PERFS AT 3734-40'. SANDED TO 3750' & 5 SX CMT. 1ST PLUG AT 800' WITH 100# HULLS - 15 SX GEL - 50 SX CMT. 2ND PLUG AT 240' WITH 100# HULLS - 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
SEP 11 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2010' OF 5 1/2".

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED SEP 06 2002

DATE 9-12-02
NO. 2003060496

Form CP-73