

To: 1 040280
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-31
API NUMBER 15-185-22,274-0000
E/2 W/2 SE SEC. 31, T 24 S, R 13 W/EX

1320 feet from S section line
990 feet from E section line

Lease Name Andrews Well # 1
County Stafford 140.11

Well Total Depth 4311 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 259

TECHNICIAN'S PLUGGING REPORT
Operator License # 3909

Operator: Pluggers, Inc.
Name & Address P.O. Box 782050
Wichita, KS 67278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pluggers, Inc. License Number 3909

Address P.O. Box 782050, Wichita, KS 67278

Company to plug at: Hour: 1:30 p.m. Day: 31 Month: 5 Year: 19 89

Plugging proposal received from Wiley Ash

(company name) Pluggers, Inc. (phone) 316-636-4390

were: 5 1/2" at 4289' Perfs at 4269-70'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 31 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top of
sand with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100
lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUN - 8 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2731' of 5 1/2" casing at
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 6-9-89

JUL 11 1989

INV. NO. 25038
5-31