

1 031005

4-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,982 - 0000

C E/2 NE NE, SEC. 27, T 24 S, R 13 W/E

4620 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5941

Lease Name Wilson Well # 1

Operator: Rosel Energy, Inc.

County Stafford 135.53

Name & Address P.O. Box 1068

Well Total Depth 4170 feet

Liberal, KS 67905-1068

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 12 Month: 4 Year: 19 89

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4139' PRTD 4160' Perfs at 4083-87'

1st plug sand back to 4030' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

APR 17 1989

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Wichita, Kansas Part None

Operations Completed: Hour: 2:20 p.m. Day: 12 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4030' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-24-89

Signed Steve Durrant (TECHNICIAN)

INV. NO. 24464