

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-22593-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 18-13S-20W  
2990 feet from S Section Line, 1740 feet from E Section Line  
Lease Name: KOHL Well #: 3  
County: ELLIS Total Vertical Depth: 4022 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 266 N MAIN ST, STE 220  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 4020       |             | 125 sx   |
| SURF   | 8.625 | 336        |             | 200 sx   |

Well Type: OIL UIC Doc:et No: \_\_\_\_\_ Date/Time to Plug: 08/17/2009 3:00 PM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: DAVE FUNK Company: QUALITY OIL WELL CEMENTING Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/17/2009 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

08/14/2009 Ran in with bit to 625'. Got to 650' and couldn't make any more hole. POOH and put mill on. Well taking water. Started drilling at 460'. Got a load of mud.

08/17/2009 Put on collar and drilled to 1780'. Got stuck. Barely got 7 joints out. Pumped 4-6 bpm and couldn't pull. Decided to plug there. Perforated @1550'. Pumped 300 sx cement to circulate inside and out. Backed off tubing and left 39 joints in hole. Tied onto 4 1/2" and pumped 100 sx cement. Max 400 psi. SIP 200 psi.

Received  
KANSAS CORPORATION COMMISSION  
**FEB 19 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Control # 20100009-001

Plugged through: TBG

District: 04

Signed Case Morris  
(TECHNICIAN)

FEB 15 2016