

To: 1 110001  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 081-20,201 -00-06  
NE SW SW SEC. 12, 'T 28 S, R 32 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corp.  
Name & Address 200 W. Douglas, Suite 300  
Wichita, KS 67202

1250 feet from S section line

4030 feet from E section line

Lease Name Koehn "A" Well # 1

County Haskell 109.11

Well Total Depth 3357 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 806

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Patrick Well Service License Number 7547

Address P. O. Box 1273, Liberal, KS 67901

Company to plug at: Hour: 9:00 am Day: 28 Month: June Year: 19 85

Plugging proposal received from Charlie Hammonds

(company name) TXO (phone) 316-265-9441

were: 4 1/2" at 3399' PBD 2754' Perfs at 2746-48'; 2736-40'; 2720-22'; 2712-14'; 2486-90'

1st plug pump 1 sack hulls and 30 sx cement to bottom

Spot through tubing with mud between plugs

2nd plug at 1780' with 50 sx cement  
solid bridge

3rd plug at 830' with 50 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Pump 150 sx cement down annulus

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:35 pm Day: 28 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 30 sx cement to bottom, 2nd plug at 1780' with 50 sx cement, 3rd plug at 830' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, and pumped 150 sx cement down

annulus.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1985

7-11-85

CONSERVATION DIVISION

Remarks: No recovery. Used Class H cement by Halliburton Surface casing protected all water  
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

INVOICED

Signed Jamael Prass  
(TECHNICIAN)

DATE 7-17-85

INV. NO. 8980 6-28 AUG 0 1 1985 SEP 1 1 1985

FORM CP-2/3  
Rev. 01-84