

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-107-19614-0000
 Spot: SEWNNE Sec 24 Twp 21 S Rng 22 ☒ E / ☐ W
4437 Feet from ☐ N / ☒ S Line of Section
1924 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 38.209046 Long: 94.939902 Date: 1/19/16-4/9/13
 Lease Name: McGrew Well #: MCG 35
 County: Linn Total Vertical Depth: 480 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>8.000</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>266 N. Main St. Ste. 266</u>	<u>STRL - Casing</u>	<u>2.000</u>	<u>475</u>	<u>475</u>	
Address 2:	<u>T1 - Tubing I</u>	<u>1.000</u>	<u>475</u>	<u>475</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 12/16/15 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: PART - Partial
 Date/Time Plugging Completed: 12/16/15 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Clear around location. Level area. Pull on 1" pipe. Pipe hung in hole Try to work loose. Try leaving strain on 1" multiple times until pipe parted. Dig around well and cut off below ground to try to get better 1". Try to unscrew 1" but couldn't. Get wash tube to try to wash over 1". Wash down about 15 ft and hit collar, wouldn't wash over collar. Get different wash tube to wash over 1". Drill over 1" to 20 ft. Fish with left hand pipe and pull 450 ft of pipe Perforate 2". Run 1" to 475 ft and pump Portland cement to surface. Pull pipe and top off well. Pump 28 sacks of cement. Well plugged.		<u>150</u>	<u>300</u>	<u>CSG - Casing</u>

Remarks: Contract No. 40376. Control No. 20150021-035. GPS'ed NAD 83 by FG. Regular Section.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☒ Yes ☐ No

District: 03

KCC WICHITA

FEB 03 2016

RECEIVED

Frank Guilfoyle
(Technician)

Form: District Plugging Report - _____