

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-01003-00-01  
Spot: W2NWSW Sec/Twnshp/Rge: 19-32S-5E  
1977 feet from S Section Line, 4796 feet from E Section Line  
Lease Name: ANDES OWWO Well #: 2  
County: COWLEY Total Vertical Depth: 1960 feet

Operator License No.: 5116  
Op Name: WELLWIN DRILLING CORPORATION  
Address: 201 W HARVEY AVE PO BOX 529  
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1871		
PROD	4.5	1821		
PROD	4.5	1871		1 SX
SURF	8.625	140		1 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/04/2015 8:00 AM  
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.  
Proposal Rcvd. from: JASON BRUNS Company: CANAAN WELL SERVICE Phone: (620) 440-4070

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS/ 30 SXS @ TD W/FILL TO 1639', SQUEEZE HOLES & CIRCUALTE 250'-0'.

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/04/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1720', HURRICANE SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 250'-251'. DID NOT TAG CEMENT. RIH W/TBG @ 1720', HURRICANE SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS CLASS A COMMON 2% CC W/50# HULLS & DISPLACED IN CASING. TAGGED CEMENT @ 1334'. SWEDGED INTO 4 1/2" CASING, HURRICANE SERVICES MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM 11-4-2015. CEMENT TICKET #100601.

Perfs:

Top	Bot	Thru	Comments
1687	1704	CSG	
Received KANSAS CORPORATION COMMISSION FEB 11 2016 CONSERVATION DIVISION WICHITA, KS			

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

220  
3-2-16

Form CP-2/3