

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20740-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 36-25S-4E
3623 feet from S Section Line, 2039 feet from E Section Line
Lease Name: GIROD Well #: 1
County: BUTLER Total Vertical Depth: 2490 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: 10500 E. BERKELEY SQUARE PKWY. S
WICHITA, KS 67206 *STE 210*

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2440		
PROD	5.5	2488		150 SX
PROD	4.5	2490		
SURF	8.625	204		145 SX
SURF	8.625	205		
SURF	8.625	213		

Well Type: SWD UIC Docket No: D17943.0 Date/Time to Plug: 01/14/2016 8:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DAN FLOWERS, WHITE & E Company: WHITE & ELLIS DRILLING Phone: (316) 208-7590

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2016 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) VERIFIED CEMENT ON BACKSIDE OF 4.5" CASING. 2) RAN IN W/WIRELINE AND SET CIBP AT 2440'. 3) RAN IN DUMP BAILER AND SPOTTED 4 SXS CEMENT ON CIBP. 4) RAN IN TUBING TO APPROX. 250' AND PUMPED 35 SKS OF 60/40 4% CEMENT WITH 0.5% CACL, CEMENT CIRCUALTED TO SURFACE. 5) WELL TOPPED OFF W/CEMENT. CASING CUT AND BURIED BELOW SURFACE.

Perfs:

Top	Bot	Thru	Comments
2452	2454		CSG

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, EL DORADO, KS. TICKET #51138

Plugged through: TBG

District: 02

KCC WICHITA *Signed* Jonathan Hill (TECHNICIAN)
FEB 22 2016
RECEIVED

no
CG-utic
3-2-16