

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-19334-00-00
Spot: SWSENE Sec/Twnshp/Rge: 20-23S-14E
1300 feet from N Section Line, 600 feet from E Section Line
Lease Name: N PEEK Well #: 3
County: WOODSON Total Vertical Depth: 1639 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2016 12:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Rcvd. from: RANDALL L. TRIMBLE Company: _____ Phone: (620) 836-2000

Proposed Plugging Method: 50' cement plug @ 1639', gel spacer, 50' cement plug 450', cement plug 250' to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2016 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1630' pumped 15 sxs cement, pulled tubing to 476' pumped 20 sxs cement, pulled tubing to 254' pumped 60 sxs cement, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
450	451		
250	251		

Remarks:

Plugged through: TBG

District: 03

Signed Mike Deffen
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
FEB 25 2016
CONSERVATION DIVISION
WICHITA, KS
Form CP-2/3
no 3-2-16

15-207-19334-0000

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 2726
 Foreman Steve Mead
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
2-17-16	1000	N Peak # 3	20	23	18	Woodson	KS	
Customer Trimble + MacLuskey Oil LLC			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 171					102	Rick		
City Gridley					112	Allen B		
State KS					145	Alan M.		
Zip Code 66852								

Job Type PTA Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Plug Well As Follows. Rig up To 2 3/8 Tubing.
Pump 10 bbls water ahead mix 300' Gel.
Spot 15 SKS AT 1630'
Spot 20 SKS AT 476'
60 SKS 254' To Surface
Total 95 SKS 60/40 Poz mix 4% Gel

Job Complete Rigdown

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	35	Mileage	3.95	138.25
C203	95 SKS	60/40 Poz mix Cement	12.75	1211.25
C206	325'	Gel 4%	.20	65.00
C306	300'	Gel (Gel Flush)	.20	60.00
C108A	4.08 ton	Ton mileage Bulk Truck	84.50	345.00
C113	3 hr	80 bbl Uac Truck	85.00	255.00
C224	3000 gals	City water	10.00 per 1000	30.00
Received KANSAS CORPORATION COMMISSION				
FEB 25 2016				
CONSERVATION DIVISION WICHITA, KS				
			Subtotal	2854.50
			7.50% Sales Tax	214.09

Authorization Witness by Brian Title Co. Rep Total 3068.59

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.