

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19716-00-00
Spot: NWNWNWNE Sec/Twnshp/Rge: 28-27S-4E
5109 feet from S Section Line, 2443 feet from E Section Line
Lease Name: CARTER Well #: 3
County: BUTLER Total Vertical Depth: 2010 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	15.5	35		
PROD	7	1914		42 SX
SURF	8.625	1315		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2016 8:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: TE-PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: AS PER KCC RULES & REGS/ WELL WAS SANDED BACK & CAPPED W/CEMENT, PERFORATE & CIRCUALTE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/08/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

MIRU, DUG OUT CELLER, WELDED & PLATED CSG STRINGS TOGETHER W/CONNECTIONS FOR VALVES. OPERATOR STATED THEY HAD SANDED WELL BACK @ 1860', & DUMP BAILED 6 SXS CEMENT ON TOP. RIH W/DUMP BAILOR, TAGGED CEMENT @ 1800'. 1/8/2016, RIH W/TBG @ 270', QUALITY WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 230 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TBG, SWEDGED INTO 7" CSG, QUALITY WELL SERVICE MIXED & PUMPED 35 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRUCLATED BETWEEN ALL STRINGS. P&A COMPLETE 1/8/2016 5:00 PM. CONSOLIDATED CEMENT TICEKT #6452.

Perfs:

Top	Bot	Thru	Comments
1914	2010	OH	KANSAS CITY

Received
KANSAS CORPORATION COMMISSION
FEB 11 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

✓
JK

no
3-2-16