

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21619-00-00
Spot: SESWSW Sec/Twnshp/Rge: 28-27S-4E
329 feet from S Section Line, 4286 feet from E Section Line
Lease Name: BORN-DONDLINGER Well #: 2
County: BUTLER Total Vertical Depth: 3331 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2500		
PROD	5.5	2915		150 SX
SURF	8.625	205		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2016 8:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: TE-PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: AS PER KCC RULES & REGS / CEMENT BOTTOM BACK @ 2390', CIRC 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/28/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2431', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC 40# HULLS & DISPLACED IN CASING. POOH W/TBG @ 280'. TAGGED CEMENT PLUG @ 2298'. RIH W/ 34" TBG ON BACKSIDE OF 5 1/2" CASING @ 267'. SWEDGED INTO 3/4" TBG, ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 60 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN 3/4" TBG. SWEDGED INTO TBG, ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 60 SXS 60/40 POZMIX 4% GEL TO SURFACE CEMENT CIRCULATED. LAYED DOWN TBG, TOPPED WELL BACK TO SURFACE W/CEMENT. P&A COMPLETE 1/28/2016 5:00 PM. CONSOLIDATED CEMENT TICKET # 51168. 120 SXS TOTAL ON TOP PLUG.

Perfs:

Top	Bot	Thru	Comments
2442	3331		CSG

Received
KANSAS CORPORATION COMMISSION
FEB 11 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

1/24
No 3-2-16