

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-22, 117-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Trans Pacific Oil Corporation KCC LICENSE # 9408 ^{2/97}
(owner/company name) (operator's)

ADDRESS 100 N. Main, Ste. 1000 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-3596

LEASE Russell WELL# 1-33 SEC. 33 T. 24S R. 13 (East/West)

C - W/2 - NW - NW SPOT LOCATION/0000 COUNTY Stafford

660 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 286 CEMENTED WITH 265 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4225 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4187-92, CIBP @ 4165, 4074-77, 3966 - 4012'

ELEVATION 1937/1942 T.D. PBTD 4165' ANHYDRITE DEPTH 810'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sd. over pfs. Cap W/2 sx cem., Rip and pull csg. Down
8 5/8" 300 #'s hulls, 10 sx gel, 50 sx cem., 10 sx gel, 100 #'s hulls, 8 5/8" wiper
plug, 125 sx cem.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Sharp PHONE# (316) 262-3596

ADDRESS 100 N. Main, Ste. 1000 City/State Wichita, KS 67202

PLUGGING CONTRACTOR D S & W Well Servicing, Inc. KCC LICENSE # 6901 ^{6/96}

(company name) (contractor's)
ADDRESS P.O. Box 231, 403 W. Front, Claflin, KS PHONE # (316) 587-3361
67530-0671

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/18/96 AUTHORIZED OPERATOR/AGENT: Gary Sharp
(signature)



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Russell #1-33
 C W/2 NW NW Sec. 33-24S-13W
 Stafford County, Kansas
 Commenced: 12-3-84
 Completed: 12-13-84
 API #15-185-22,117
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	100	Sand	Ran 7 joints (279') new, 23#, 8 5/8" surface casing. Set at 286' with 165 sxs Common, 2% gel, 3% cc. Cement did not circulate.
100	251	Clay	
251	291	Sand, Shale	
291	1239	Sand, Clay	100 sxs Common, 3% cc, top out at 250'. Job by Buie, ticket #3534. Plug down at 6:15 a.m. on December 4, 1984.
1239	4225	Lime, Shale T.D.	

RTD 4225'

Ran 101 joints (4241') new, 4 1/2" production casing. Set at 4223' with 25 sxs Lite and 125 sxs Latex. Job by Halliburton. Plug down at 11:15 a.m. on December 13, 1984.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:

3/22/88



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

March 21, 1996

Trans Pacific Oil Corporation
100 N Main Ste 1000
Wichita KS 67202

Russell #1-33
API 15-185-22,117
660 FNL 330 FWL
Sec. 33-24S-13W
Stafford County

Dear Gary Sharp,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760