

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15155200640000
Spot: CNWNENW Sec/Twnshp/Rge: 27-23S-4W
4950 feet from S Section Line, 3650 feet from E Section Line
Lease/Unit Name: BANZ Well Number: 3
County: RENO Total Vertical Depth: 3430 feet

Operator License No.: 5118 Conductor Pipe: Size feet:
Operator Name: TGT PETROLEUM CORPORATION Surface Casing: Size 8.62 feet: 653
Address: 7570 W 21ST ST N. STE1010D Production: Size 4.5 feet: 3426 *111.48*
WICHITA, KS 67275 *8/30* Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 8/30/00 8:30:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: ELDON FOLMNSBEE Company: TGT PETROLEUM CORPORATION Phone: (316) 773-2266

Proposed Plugging Method: SET C.I.B.P. AT 3330' AND TOP WITH 4 SXS. CEMENT. SHOOT PIPE OFF. PULL PIPE TO 700' AND SPOT 35 SXS. CEMENT. PULL PIPE TO 250' AND CIRCULATE CEMENT TO THE SURFACE. PERFORATIONS FROM 3338' TO 3430'.

Plugging Proposal Received By: DAVE WERTZ Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 08/30/2000 2:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SAT C.I.B.P. AT 3275' AND TOPPED WITH 4 SXS. CEMENT. SHOT PIPE OFF AT 2312'. PULLED PIPE TO 692' AND SPOTTED 35 SXS. CEMENT. PULLED PIPE TO 271' AND CIRCULATED 95 SXS. CEMENT TO THE SURFACE. TOPPED OFF PLUG WITH ONE YARD SLURRY ON 09/12/00.

RECEIVED
KCC DISTRICT #2

SEP 14 2000

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED. INVOICE #7553

Plugged through: CSG

District: 02

Signed Michael Wilson

(TECHNICIAN)

INVOICED
9/18/00
2001060701