

2 100542

10-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 155-21,105-0000
SW NW SE, SEC. 27, T 23 S, R 4 WXX

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8740

Lease Name O'Neal Well # 3

Operator: Bramwell Petroleum
Name & Address: RR #2
Spivey, KS 67142
316-532-2770

County Reno 111.09

Well Total Depth 3418' 3400' PB feet

Conductor Pipe: Size 10-3/4 feet 253'/175 SX

Surface Casing: Size 8-5/8 feet 623'/160 SX

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well 5-1/2 3418'/125 SX D&A

Other well as hereinafter indicated perf 3341-3346'

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:00a Day: 20 Month: 10 Year: 19 89

Plugging proposal received from Don Bramwell

(company name) Bramwell Petroleum (phone) _____

were: Sand 50' above to perfs - 5 sx cmt - shoot & pull 5-1/2" - pump 200 sx
cement - mix w/500# hulls.

Plugging Proposal Received by W.K. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 Day: 20 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT Sanded to 3290' w/5 sx cmt on top - shot & pulled 2623'
of 5-1/2" and pumped from top 200 sx cmt w/500# hulls.

NOV 7 1989
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Allied #6835 60/40 6% 200# open - 50# shutin
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and my agent) observe this plugging.

DATE 11-7-89
INV. NO. 26372

Signed J.L. Sanders (TECHNICIAN)