

2 100541

10-20 15-155-20098-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 159-21,056
N2 NW SE, SEC. 27, T 23 S, R 4 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 8740

_____ feet from S section line
_____ feet from E section line

Operator: Bramwell Petroleum
Name & Address RR #2
Spivey, KS 67142
316-532-2770

Lease Name O'Neal Well # 1
County Reno 111.15

Well Total Depth 3420' 3410 PB feet

Conductor Pipe: Size 10-3/4" feet 256'/225 SX

Surface Casing: Size 8-5/8" feet 604'/100 SX
5-1/2" 3418'/125 SX
D&A

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____

Other well as hereinafter indicated _____ perfs 3337'-42' 20 holes

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Great Bend KS 67530

Company to plug at: Hour: 1:00 Day: 20 Month: 10 Year: 19 89

Plugging proposal received from Don Bramwell

(company name) Bramwell Petroleum (phone) _____

were: Sand 50' above top perfs - 5 sx cmt - shoot & pull 5-1/2" - pump from
top 200 sx - cement w/500# hull mixed.

Plugging Proposal Received by Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 Day: 20 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT Sanded to 3280' & dumped 5 sx cement - shot & pulled 1990'
of 5-1/2" - pumped 25 sx w/100# hulls - well circ fresh water - pumped 131 more
sx cement - well stopped circulating - pumped 46 sx cmt - shut in well.

Remarks: Allied #6836 60/40 6% 300# open 50# SI
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

DATE 11-7-89

Signed J.L. Sanders
(TECHNICIAN)

INV. NO. 26371 WK

NOV - 7 1989
11-7-89
CONSERVATION DIVISION
WICHITA, KANSAS