

2 040347

7-30-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 095-21,571-0000

C SW SW, SEC. 8, T 27 S, R 5 W/EX

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5248

Lease Name Circle S Angus Well # 1

Operator: Olympic Petroleum Company

County Farm Kingman 114.73

Name & Address 2121 S. Columbia Avenue

Well Total Depth 3530 feet

Tulsa, OK 74114

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address Wichita, Kansas

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Jerry

(company name) Red Tiger (phone)

were: 35 sxs at 450', 35 sxs at 260', 25 sxs at 60', 10 sxs in rathole

Plugging Proposal Received by John Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 20:15 Day: 30 Month: 7 Year: 1987

ACTUAL PLUGGING REPORT

Open ended drill pipe was run to 450 where 35 sxs of cement was spotted. The drill pipe was pulled to 260' and another 35 sxs of cement was spotted.

The drill pipe was pulled from the hole and a rubber plug was pushed to 60' and the

hole was circulated with 25 sxs of cement. The rathole was circulated with 10 sxs

of cement. AUG 4 1987

8-4-87

Remarks: Wichita, Kansas United #3322 60/40 4% gel

(If additional description is necessary, use BACK of this form.)

INVOICED (date/did not observe this plugging.)

DATE 8-5-87

Signed [Signature] (TECHNICIAN)

INV. NO. 17715