

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-21050-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 36-19S-15W
932 feet from S Section Line, 4989 feet from E Section Line
Lease Name: EWING TWIN Well #: 1
County: BARTON Total Vertical Depth: 3317 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	1	608		
PROD	5.5	3312		
SURF	8.625	895		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/03/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement, 13 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1500' and 950'. Ran tubing to 3300' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 900' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 450'. Circulated cement to surface on casing w/60 sx cement. Pulled tubing. Tied to casing and had circulation on surface pipe. Pumped 245 sx cement into surface pipe and ran out of cement. Shut down for the day.
02/04/2016- Cut off braden head and ran 1" ^{liner} tubing to 608'. Circulated cement to surface w/50 sx cement. Topped off casing w/15 sx cement.

GPS: 38.34973 -098.93916

Received
KANSAS CORPORATION COMMISSION
FEB 19 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE SMOKEY VALLEY RESOURCES FEE FUND PROJECT CONTROL # 20160016003

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

FEB 15 2016