

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-21131-00-00
Spot: NESESE Sec/Twnshp/Rge: 35-19S-15W
983 feet from S Section Line, 299 feet from E Section Line
Lease Name: BEAHM Well #: 1
County: BARTON Total Vertical Depth: 3652 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| L1 | 1 | 425 | | |
| PROD | 5.5 | 3652 | | |
| SURF | 8.625 | 892 | | |

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/01/2016 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed
Plugging
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement, 14 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/02/2016 1:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1500' and 950'. Ran tubing to 3350' and pumped 14 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 900' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 450'. Circulated cement to surface w/85 sx cement. Lost circulation on surface pipe. Shut down for the day. 02/02/2016- Cut off braden head and ran 1" ^{tubing} liner to 425'. Circulated cement to surface w/50 sx cement. Topped off casing w/25 sx cement.

GPS: 38.34988 -098.94125

Received
KANSAS CORPORATION COMMISSION
FEB 19 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE SMOKEY VALLEY RESOURCES FEE FUND PROJECT CONTROL # 20160016001

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

FEB 15 2016

Form CP-2/3