

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22432-00-00
Spot: E2NWSWSW Sec/Twnshp/Rge: 36-19S-15W
990 feet from S Section Line, 405 feet from W Section Line
Lease Name: EWING Well #: 3
County: BARTON Total Vertical Depth: 3564 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	1	608		
PROD	4.5	3563		
SURF	8.625	890		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement, 13 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 950'. Ran tubing to 3379' and pumped 8 sx gel followed by 40 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 450'. Circulated cement to surface on casing w/375 sx cement and 200 # hulls with circulation on surface pipe. Pulled tubing. Tied to casing and lost circulation on surface pipe. Pumped 105 sx cement into surface pipe and ran out of cement. Had circulation on surface pipe on the last 10 sx cement before running out of cement. Shut down for the day.
02/06/2016- Cut off braden head and ran 1" ^{tubing} liner to 608'. Circulated cement to surface w/50 sx cement. Topped off casing w/15 sx cement.

GPS: 38.34986 -098.93880

Perfs:

Received
KANSAS CORPORATION COMMISSION
FEB 19 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE SMOKEY VALLEY RESOURCES FEE FUND PROJECT CONTROL #20160016004

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

FEB 15 2016