

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-21139-00-00  
Spot: W2SESE Sec/Twnshp/Rge: 34-19S-14W  
633 660 feet from S Section Line, 847 feet from E Section Line  
Lease Name: CITY OF GREAT BEND Well #: 1  
County: BARTON Total Vertical Depth: 2330 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 266 N MAIN ST, STE 220  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2330		
SURF	8.625	794		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/09/2016 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed  
Plugging  
Method:

Ordered 300 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/10/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Rods and tubing in well. Pulled 94 rods and 74 joints of tubing. Perforated at 1450' and 850'. Ran tubing to 2200' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 40 sx cement w/200 # hulls. Pulled tubing to 850' and pumped 30 sx cement w/100 # hulls. Pulled tubing to 450'. Circulated cement to surface w/110 sx cement. Pulled tubing. Tied on to casing and circulated cement to surface on surface pipe w/160 sx cement. 02/10/2016- Cut off braden head and topped off w/15 sx cement.

GPS: 38.34899 -098.85093

Perfs:

Received  
KANSAS CORPORATION COMMISSION  
**FEB 19 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY WELL SERVICES SMOKEY VALLEY RESOURCES FEE FUND PROJECT CONTROL# 20160016002

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

FEB 15 2016