

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22592-00-00
Spot: S2NENWSE Sec/Twnshp/Rge: 32-31S-3W
2060 feet from S Section Line, 1650 feet from E Section Line
Lease Name: ERSKINE Well #: 4-32
County: SUMNER Total Vertical Depth: 4010 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4011	1852	220 SX
SURF	8.625	266		225 SX
T1	2.375	3941		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/15/2016 12:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/15/2016 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3870' AND CAPPED WITH 2 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 1852' AND PULLED TO 552' WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 343', WHERE CEMENT WAS CIRCULATED TO SURFACE. THE CASING WAS PULLED AND 15 SKS OF CEMENT WAS USED TO TOP OFF THE HOLE.

Perfs:

Top	Bot	Thru	Comments
3930	3940	CSG	
3922	3940		

Remarks: HURRICANE SERVICES INC CLASS A CEMENT

Plugged through: CSG

District: 02

Signed _____


(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

202-26-16

JK