

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-20873-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 20-31S-8W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HONN B Well #: 1
County: HARPER Total Vertical Depth: 4413 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S MAIN ST
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4402	3010	100 SX
SURF	8.625	253		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/25/2016 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET ABOVE THE PERFS AT 4340' AND CAPPED WITH 2 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 3010' AND PULLED TO 1350', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CEMENT WAS SPOTTED IN PLACE. THE CASING WAS PULLED TO 300', WHERE CEMENT WAS CIRCUALTED TO SURFACE WITH 110 SKS OF CEMENT. REMAINING CASING PULLED AND CEMENT TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4402	4412	OH	

Remarks: QWS CLASS A CEMENT.

Plugged through: CSG

District: 02

Signed 
(TECHNICIAN)

KCC WICHITA
FEB 22 2016
RECEIVED

JK *no 2-26-16*