

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-20629-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 36-23S-15W
2303 feet from S Section Line, 550 feet from W Section Line
Lease Name: MUNZ Well #: 1
County: PAWNEE Total Vertical Depth: 4210 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S MAIN ST
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4208	840	WITH 125 SX CMT
SURF	8.625	253		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/12/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3966' WITH 5 SX CMT. PLUG AT 960' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2016 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

BOTTOM PLUG AT 3980' WITH 5 SX CMT. 1ST PLUG AT 840' WITH 10 SX GEL & 50 SX CMT. CASING PARTED AT THIS DEPTH. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 50 SX CMT. DID NOT CIRCULATE. 2/15/16: CHECKED CMT TOP & FOUND IT AT 92'. PUMPED 20 SX CMT & CASING WAS FULL. 92' PLUG WITNESSED BY KEN SCOFIELD.

Perfs:

Top	Bot	Thru	Comments
4118	4122		
4016	4040		

Received
KANSAS CORPORATION COMMISSION
FEB 19 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
FEB 16 2016
KCC DODGE CITY

Form CP-2/3
70
2-26-16
KMS