

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-20306-00-00
Spot: W2E2W2NW Sec/Twnshp/Rge: 13-33S-39W
4006 feet from S Section Line, 4470 feet from E Section Line
Lease Name: CHRISTOPHER J A Well #: 9-13
County: STEVENS Total Vertical Depth: 2955 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2955	0	WITH 550 SX CMT
SURF	8.625	710		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/18/2016 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 1. MIRUSU, unflange well and NU BOP. Spot 2 3/8" workstring. 2. Trip in hole with tubing and tag RBP @ 2723'; circulate hole with mud and cap RBP with 10 sacks cement. 3. Pull up hole with tubing @ 1700' and spot 30 sacks Class "C" cement to cover Anhydrite. 4. Pull up hole with open ended tubing @ 1100'; mix and spot 25 sacks cement with 50# cotton seed hulls to cover Glorietta leak. POH and wait on cement. 5. Load casing and test @ 300 psi. Perf squeeze hole @ 750'. 6. Breakdown perfs and establish circulation to surface on 8 5/8" outlet. Mix and pump 260 sacks Class "C" cement and circulate to surface and leave both casing strings full to surface. 7. RDMOSU. Cut and cap well.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2016 4:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

TAG RBP @ 2723' WITH 10 SX CMT. 1ST PLUG AT 1701' WITH 30 SX CMT. 2ND PLUG AT 1102' WITH 25 SX CMT W/1/2 SX CC. WOC 3 HOURS. PRESSURE TO 300 PSI. PERFORATE AT 750'. TOC @ 850'. 2RD PLUG PUMPED 270 SX CMT DOWN CASING & CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2800	2910		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]

RECEIVED
FEB 24 2016
KCC DODGE CITY [Signature]

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

FEB 25 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
2-26-16