

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-20058-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 20-31S-38W
1307 feet from S Section Line, 4021 feet from E Section Line
Lease Name: LIGHT Well #: 2-29
County: STEVENS Total Vertical Depth: 2900 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2680		
PROD	5.5	2899	0	WITH 300 SX CMT
SURF	8.625	523		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/22/2016 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 1. MIRUSU. Spot 2 3/8" workstring. NU BOP. Pick up 5.5" tbg set CIBP. Run in hole and set CIBP @ 2680' or above sand fill. 2. Release from tubing, mix and pump 180 Class "C" cement with 100# cotton seed hulls, POH with tubing and WOC. 3. Tag top of cement (1150' or higher). Load and test casing @ 300 psi. 4. Rig up wireline truck and perforate squeeze holes @ 600'. 5. Breakdown perfs and establish circulation to surface on 8 5/8" outlet. Mix and pump 225 sacks Class "C" cement and circulate to surface. 6. RDMOSU. Cut and cap well.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 02/22/2016 11:30 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

2/19/16: CIBP @ 2680'. 1ST PLUG AT 2680' WITH 180 SX CMT. 2/22/16: TAGGED CMT AT 1470'. PRESSURED TO 300 PSI. PERFORATE AT 600'. PUMPED 235 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2731	2889		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed [Signature]

RECEIVED
FEB 24 2016
KCC DODGE CITY [Signature]

(TECHNICIAN) Received
JSA
STATE CORPORATION COMMISSION
FEB 25 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
2-26-16