

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-20968-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 7-27S-32W
4040 feet from S Section Line, 4064 feet from E Section Line
Lease Name: ROGGE Well #: 2
County: HASKELL Total Vertical Depth: 2790 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2570		
PROD	4.5	2790	0	WITH 625 SX CMT
SURF	8.625	491		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/05/2016 10:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2570'. PLUG AT 2570' WITH 100 SX CMT WITH 100# HULLS IN FIRST 30 SX CMT. PLUG AT 1000'-0' WITH 70 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/05/2016 4:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 2570'. 1ST PLUG AT 2570' WITH 100 SX CMT W/3% CC. WAIT 2 HOURS. TOC @ 1300'. 2ND PLUG AT 1291'-0' WITH 85 SX CMT. CMT CIRCULATED. TOPPED OFF WITH 10 SX CMT. BACKSIDE TOOK 10 SX CMT. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2622	2692		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
FEB - 8 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
FEB 10 2016
CONSERVATION DIVISION,
WICHITA, KS

Form CP-2/3

no
2-26-16