

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-187-20224-00-00  
Spot: E2 Sec/Twnshp/Rge: 26-27S-40W  
2676 feet from S Section Line, 1328 feet from E Section Line  
Lease Name: SMITH ABBIE E Well #: 2-26  
County: STANTON Total Vertical Depth: 2755 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2754	0	WITH 600 SX CMT
SURF	8.625	681		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2016 9:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TAG SAND FILL @ 2480'. PUMP 150 SX WITH CC. WOC. TAG CMT. PUMP 150 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/23/2016 5:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

TAGGED SAND FILL AT 2425'. 1ST PLUG AT 2425' WITH 150 SX CMT WITH CC. WOC. TAGGED TOC @ 1920'. 2ND PLUG AT 1900' WITH 155 SX CMT TO SURFACE. BACKSIDE TOOK 10 SX CMT. 20 SX CMT TO FILL UP.

Perfs:

Top	Bot	Thru	Comments
2531	2639		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]

RECEIVED  
FEB 24 2016  
KCC DODGE CITY

(TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

FEB 25 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

20  
2-26-16