

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40161-00-00
Spot: NESESESE Sec/Twnshp/Rge: 18-33S-10E
341 feet from S Section Line, 227 feet from E Section Line
Lease Name: BURDEN Well #: 2
County: CHAUTAUQUA Total Vertical Depth: 1566 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	1500		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 800' and 500'. Run 1" back in and spot 50' plug of cement at 800'. Pull up to 500' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 01/28/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1500' gelled hole and spotted 10 sack plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" to 900' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 160 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1400	1410		


RECEIVED
KCC DIST # 3
FEB 18 2016
CHANUTE, KS
DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

no 2-26-16