

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-24031-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 18-23S-4E
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: ENSZ Well #: 1
County: BUTLER Total Vertical Depth: 2900 feet

Operator License No.: 34811
Op Name: KANSAS PETROLEUM RESOURCES, LL
Address: 200 E. 1ST STREET, STE 307
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2414		
PROD	5.5	2873		150 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2016 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: ROD ANDERSEN Company: KANSAS PETROLEUM RESOURCE Phone: (316) 204-3359

Proposed Plugging Method: Cement Plug at bottom and cement plug at 50' below surface casing and cement inside and out.

Plugging Proposal Received By: JONATHAN HILL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2016 11:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) GEMINI WIRELINE SERVICES RAN IN W/ CIBP ON WIRELINE AND SET AT 2414'.
2) DUMP BAILED 5 SKS CEMENT ON TOP OF CIBP. 3) LOADED HOLE AND
PRESSURED TEST CASING AND CIBP TO 300 PSI. PRESSURE HELD. 4) RAN IN
W/WIRELINE AND PERFORATED W/4 SHOTS AT 270'. 5) TIED INTO 5.5" CASING
AND ESTABLISHED CIRCULATION. PUMPED 85 SKS CLASS A 60/40 4% CEMENT
AND CIRCULATED CEMENT TO SURFACE. WELL SHUT IN.

Perfs:

Top	Bot	Thru	Comments
2767	2812	CSG	
2450	2510		

Remarks: CEMENTING COMPLETED CONSOLIDATED OIL WELL SERVICES, EL DORADO, KS. TICKET #51150.
PLUGGED FOR COMPLIANCE W/ 82-3-111.

Plugged through: CSG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

KCC WICHITA
FEB 22 2016
RECEIVED

Form CP-2/3
no
2-26-16