

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22885-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 3-29S-4E
175 feet from S Section Line, 2013 feet from E Section Line
Lease Name: HOWARD Well #: 3
County: BUTLER Total Vertical Depth: 1955 feet

Operator License No.: 35148
Op Name: KRUG, CARROLL R.
Address: 300 MAPLE ST. BOX 100
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1955		180 SX
SURF	8.625	200		70 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2016 8:00 AM
Plug Co. License No.: 34798 Plug Co. Name: VIKING PRODUCTION LLC
Proposal Rcvd. from: CARROL KRUG Company: CARROL KRUG Phone: (620) 218-1396

Proposed Plugging Method: AS PER KCC RULES & REGS/ CEMENT BACK @ 1825', CIRCUALTE CEMENT 250'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 01/21/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1903', VIKING PRODUCTION ESTABLISHED CIRCULATION, MIXED & PUMPED 14 SXS CLASS A COMMON & DISPLACED IN CASING. 1/19/2016, TAGGED CEMENT PLUG @ 1792'. 1/21/2016, RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 250'. RIH W/TBG @ 250', VIKING ESTABLISHED CIRCULATION, MIXED & PUMPED 170 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #51165.

Perfs:

Top	Bot	Thru	Comments
1876	1881		CSG

Received
KANSAS CORPORATION COMMISSION
FEB 11 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: OPERATOR REQUIRED TO PLUG WELL DUE TO EXPIRED LICENSE.

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

JK

JK
2-26-16