

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22934-00-01
Spot: NENWNE Sec/Twnshp/Rge: 10-29S-4E
4964 feet from S Section Line, 1916 feet from E Section Line
Lease Name: HOWARD Well #: 4
County: BUTLER Total Vertical Depth: 2900 feet

Operator License No.: 35148
Op Name: KRUG, CARROLL R.
Address: 300 MAPLE ST. BOX 100
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		1778		
PROD	4.5	2014		
SURF	8.625	205		200 SX
T1	2.375	1778		

Well Type: EOR UIC Docket No: E24915.2 Date/Time to Plug: 01/14/2016 8:00 AM
Plug Co. License No.: 34798 Plug Co. Name: VIKING PRODUCTION LLC
Proposal Rcvd. from: CARROL KRUG Company: CARROL KRUG Phone: (620) 218-1396

Proposed Plugging Method: AS PER KCC RULES & REGS / CEMENT BACK @ 1840', CIRCUALTE CEMENT 250'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 01/21/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1903', VIKING PRODUCTION ESTABLISHED CIRCULATION, MIXED & PUMPED 13 SXS CLASS A COMMON & DISPLACED IN CASING. 1/19/2016, TAGGED CEMENT PLUG @ 1848'. 1/21/2016, RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 250'. RIH W/TBG @ 250', VIKING ESTABLISHED CIRCULATION, MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #51164.

Perfs:

Top	Bot	Thru	Comments
1894	1900	CSG	

Received
KANSAS CORPORATION COMMISSION
FEB 11 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: E-24,915, OPERATOR REQUIRED TO PLUG WELL DUE TO EXPIRED LICENSE.

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

20
2-26-16
CC-KIC
Form CP-2/3