

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-119-21307-00-00
 Spot: SESW Sec/Twnshp/Rge: 7-33S-29W
352 feet from S Section Line, 3150 feet from E Section Line
 Lease Name: MICKEY Well #: 1-7
 County: MEADE Total Vertical Depth: 6400 feet

Operator License No.: 31458
 Op Name: HJ, INC.
 Address: 70 N FARMLAND RD
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5790		
CIBP		6210		
PROD	5.5	6400	2934	WITH 350 SX CMT
SURF	8.625	1532		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2016 9:00 AM
 Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
 Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP BOTTOM OR CIBP @ 4830' WITH 2 SX CMT. PLUG AT 1580' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 02/04/2016 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP BOTTOM WITH 25 SX CMT & 200# HULLS. PRESSURED TO 500# & HELD. 1ST PLUG AT 1580' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6250	6257		
6246	6248		
6093	6101		
6030	6048		
5926	5944		
5890	5900		
5878	5882		
5839	5842		
4866	4873		

Remarks: USED CLASS A CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
 FEB 10 2016
 KCC DODGE CITY

Signed Larry Harris ECRS
 Received (TECHNICIAN)
 KANSAS CORPORATION COMMISSION

FEB 16 2016
 CONSERVATION DIVISION
 WICHITA, KS

FEB 16 2016
 CONSERVATION DIVISION
 WICHITA, KS
 2-16-2016

Form CP-2/3

KMS