

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20807-00-01
Spot: S2NWNE Sec/Twnshp/Rge: 36-25S-4E
4290 feet from S Section Line, 1980 feet from E Section Line
Lease Name: GIROD A OWWO Well #: 1
County: BUTLER Total Vertical Depth: 2500 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		
PROD	4.5	2499		570 SX
SURF	8.625	203		145 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2015 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: HUNT HAWKINS Company: HAWKINS OIL Phone: (918) 382-7743

Proposed Plugging Method: Set CIBP @ 1,975', bail 2 sx on top. Squeeze shots @ 195' & circ cement(570 sx run on the 4.5", Temp. Survey found top @ 200'.)

Plugging Proposal Received By: JONATHAN HILL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2015 11:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) RAN IN ON WIRELINE AND SET CIBP AT 1975', BAILED 2 SKS CEMENT ON TOP.
2) LOADED HOLE W/ WATER, PERFORATED AT 195'. 3) RAN IN HOLE W/ 7 JOINTS OF TUBING, LOADED HOLE, NO CIRCULATION. 4) PULLED OUT OF HOLE, TIED INTO 4.5" CASING AND PUMPED 80 SKS 60/40 4% CEMENT, CIRCUALTED CEMENT TO SURFACE. 5) CHECKED TOP PLUG ON 12/7/2015, CEMENT APPROX. 24' DOWN. 6) WELL TOPPED OFF WITH READY MIX, PIPE CUT BELOW GROUND AND BURIED.

Perfs:

Top	Bot	Thru	Comments
2002	2008		CSG

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, EL DORADO, KS. TICKET #51903. PLUGGED DUE TO COMPLIANCE W/82-3-111.

Plugged through: CSG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

KCC WICHITA
FEB 22 2016
RECEIVED

Form CP-2/3
No 2.26.16