

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40625-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 11-35S-11E
3794 feet from S Section Line, 3205 feet from E Section Line
Lease Name: RAY Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 1134 feet

Operator License No.: 34907

Op Name: GREEN, FRANK

Address: PO BOX 235

CHAUTAUQUA, KS 67334

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	7		0 SX
SURF	10	12		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/18/2015 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Recvd. from: FRANK GREEN

Company:

Phone: (620) 249-1981

Proposed
Plugging
Method:

Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

Witness Type: PARTIAL

Date/Time Plugging Completed: 11/19/2015 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1100' gelled hole and spotted 20 sack plug. Pulled 1" and pulled 340' of 7" casing. Ran 1" back into 700' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 240 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1111	1124		
RECEIVED KCC DIST # 3 FEB 18 2016 CHANUTE, KS DS			

Remarks:

Plugged through: CSG

District: 03

Signed

Duane A Sims

(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

20
2-26-16