

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22695-00-00
Spot: SWSW Sec/Twnshp/Rge: 6-20S-10W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: SCHARTZ Well #: 1A-6
County: RICE Total Vertical Depth: 3390 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3275		
PROD	5.5	3389	2629	80 SX
PROD	5.5	3390		80 sx cement
SURF	8.625	385		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2016 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-0895

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/11/2016 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG CIBP AT 3275'. SAND LKC PERFS TO 3010' AND CAPPED WITH 5 SX'S CEMENT. CUT CASING OFF AT 2629' AND PULLED TO 1300' AND PUMPED 35 SX'S COMMON CEMENT WITH 2% CC. PULL CASING ON UP TO 900'. WAIT 1 HOUR AND TAGGED CEMENT AT 1144'. PUMPED 35 SX'S AT 900', PULLED CASING TO 435' AND CIRCUALTED CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3276	3320	CSG	
3275	3319	CSG	
3080	3196	CSG	

Remarks: DENIED TA WELL DUE TO HFLD. COPELAND #C-43679.

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

no
2-26-16