

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23112-00-00
Spot: NWNENW Sec/Twnshp/Rge: 22-33S-6E
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: DRAKE A Well #: 3
County: COWLEY Total Vertical Depth: 3150 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3149	440	200 SX
SURF	8.625	208		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2015 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DONALD L. BUTLER Company: DOUBLE D OIL CO Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/21/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2830', DUMP BAILED 3 SXS CEMENT ON TOP OF SAND.
CUT CASING @ 440', LAYED DOWN 11 JOINTS 4 1/2" CASING. RIH W/TBG @ 350',
MCPHERSON DRILLING PUMPED 116 SXS CLASS A COMMON TO SURFACE.
CEMENT CIRCULATED. DANIELS REDI MIX TICKET #33809 & 33812.

Perfs:

Top	Bot	Thru	Comments
3047	3053	CSG	
2890	2894	CSG	

Remarks: COMPLIANCE/10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)
KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

770
2-26-16

JK